

Republic of the Philippines
Department of Education
REGIONAL OFFICE NO. VIII (EASTERN VISAYAS)
Government Center, Candahug, Palo, Leyte

TO: _____

PR NO: 20-11-744
DATE: November 27, 2020
GSU

REQUEST FOR QUOTATION

Sealed proposal plainly marked Proposal to supply materials to the Government subject to terms and condition contained herein will be received at the BAC office, Dep.Ed. RO 8, Government Center, Candahug, Palo, Leyte until _____ and publicly opened in the presence of the members of the committee on Awards or their Authorized representative and the bidders and or their representative.

QTY	UNIT	ARTICLE	UNIT PRICE	TOTAL
1	LOT	Procurement for Labor and Materials for the Repair of Administrative Division Conference Room <i>*See attached detailed PROGRAM OF WORK</i>		
For more details on the procurement contact the GENERAL SERVICES UNIT, ADMIN. DIVISION , DepEd Regional Office VIII, Candahug, Palo, Leyte 6501 Contact No/s. (053) 832-4631 / Email: gsu.region8@deped.gov.ph				

ABC= Php600,00.00

Deadline of Submission of RFQ: December 2, 2020

- Requirements in Canvassing on Accredited Stores/Suppliers**
(Please comply with the following for ONLINE PAYMENT purposes)
- 1. Electronic copy of bank account, preferably Land Bank of the Philippines
 - 2. Mayor's Permit/Business Permit
 - 3. DTI Permit
 - 4. Tax Certification/BIR Certificate
 - 5. Philgeps Registration/ Certificate
 - 6. Exact Location/ Address of the Store/ Establishment
 - 7. Picture of Signage/Billboard of the Store/ Establishment
 - 8. Statement of the Prospective Bidder that it is not blacklisted or barred from bidding by the Government or any of its agencies, offices, corporations or LGUs as required in Item No. 9.2 of COA Circular No. 2012-001 dated June 14, 2012.
 - 9. Sworn Affidavit of he bidder that it is not related to the Head of Procuring Entity (HOPE) by consanguinity or affinity up to the third civil degree as required in the same COA Circular.

TERMS AND CONDITION:

Place of delivery, Dep.Ed. RO 8, Government Center, Candahug, Palo, Leyte within immediate days from receipt of the order.
Absence and/ or failure on the part of the bidder(s) to appear in the opening of the sealed bids shall be considered as a waiver.

I HEREBY CERTIFY that I am in a position to furnish the above articles and quantities stated except those marked " NONE". These terms and conditions specified above and at the back of this form are hereby offered.

Authorized Signature Over Printed Name:

Bidder: _____ TIN No. _____

Contact No: _____

Canvassed by: _____

Approved:

OPENED:	DATE: _____
	DATE: _____
	DATE: _____
	DATE: _____

(SGD)
ARNULFO M. BALANE, CESO V
Director III / BAC Chairman

NOTE: Place this inside the official envelope sealed with your signature across the opening part and personally deliver this to DepEd RO VIII (Attn: ARNULFO M. BALANE, CESO V, BAC Chairman)



LEAD, EMPOWER, AND ACHIEVE THROUGH DATA-DRIVEN DECISIONS
...where LEADers create great schools

(053) 323-3156 | region8@deped.gov.ph | BAC

Republic of the Philippines
Department of Education
 DEPED REGIONAL OFFICE NO. VIII
 Gov't. Center, Candaug, Palo, Leyte
 ISO 9001:2015 CERTIFIED

PROJECT : REPAIR AND REHABILITATION OF ADMINISTRATIVE DIVISION CONFERENCE ROOM
 LOCATION : DEPED REGIONAL OFFICE VIII
 OWNER : DEPARTMENT OF EDUCATION
 SUBJECT : APPROVED AGENCY ESTIMATE

ITEM NO.	DESCRIPTION	UNIT	QTY	UNIT COST		TOTAL COST		GRAND TOTAL
				MATERIAL	LABOR	MATERIAL	LABOR	
1.0000	GENERAL REQUIREMENTS							
	Mobilization/Temporary Structures, Utilities and Services/Demobilization	lot	1.00					
	Safety and Health	lot	1.00					
	Sub-total							
2.0000	DEMOLITION WORKS							
	Removal of Existing Wall	sq.m	20.70					
	Removal of Ceiling	sq.m	38.76					
	Sub-total							
3.0000	EARTHWORKS							
	Excavation	cu.m	11.63					
	Backfilling and Compaction	cu.m	11.63					
	Sub-total							
4.0000	CONCRETE WORKS							
	Portland Cement	bag	90.00					
	Crushed Gravel 3/4"	cu.m	9.00					
	Washed Sand	cu.m	4.50					
	Slab Reinforcement Steel Bar use 10 mm Diam. @ 0.60m. x 0.60m. SP CD. Bothways.							
	10mm x 6m RSB	pcs.	22.00					
	Tie wire	kgs.	1.00					
	Wall Footing Reinforcement Steel Bar use 3-12 mm Diam. for Main Bars and 10 mm. diam ties spcd. @ 0.40 m.							
	10mm x 6m RSB	pcs.	6.00					
	12mm x 6m RSB	pcs.	10.00					
	Tie wire	kgs.	1.00					
	Concrete Post Reinforcement Steel Bar use 4-12 mm Diam. for Main Bars and 10 mm. diam ties spcd. @ 6 - 0.05 m., 3- 0.10m. and .20m. Both ends.							
	10mm x 6m RSB	pcs.	16.00					
	12mm x 6m RSB	pcs.	12.00					
	Tie wire	kgs.	4.00					
	Concrete Footing							
	12mm x 6m RSB	pcs.	7.00					
	Tie wire	kgs.	4.00					
	Sub-total							
5.0000	MASONRY WORKS							
	USE 100 MM. THK. CHB, AND 10 MM. Ø RSB, @ 40 CM, VERT. AND 2 HOR., WALL REINFORCEMENT							
	10mm x 6m RSB	pcs.	91.00					
	Tie wire 0.40 m.	kgs.	8.00					
	CHB 4" thk	pcs.	988.00					
	Glass Louver Blocks 10"x10"	pcs.	42.00					
	Mortar Class "A"							
	Cement	bags.	65.00					
	Sand	cu.m.	3.51					
	Plastering Class "A" @ .20m thk., 2 face							
	Cement	bags.	58.50					
	Sand	cu.m.	3.25					
	Sub-total							
6.0000	TILE WORKS							
	Flooring							
	Unglazed Floor Tiles 60cm x 60cm	pc	108.00					
	Tile Adhesive 25 kg/bag	bag	27.00					
	Tile Grout 5 kg/bag	bag	8.00					
	Cement	bags.	15.00					
	Sand	cu.m.	0.81					
	Sub-total							
7.0000	DOORS, WINDOWS AND GLASS FRAME PARTITION							
	Analok Frame Glass Partion with Doors, Tentled, and Accessories	set	1.00					
	Sliding Aluminum Window	set	4.00					
	Sub-total							
8.0000	ROOFING WORKS							
	L.C 100 x 50 x 15 x 4.5 @ 6m.	pcs.	10.00					
	L 75 x 75 x 6.35mm @ 6m.	pcs.	10.00					
	L 50 x 50 x 6.35mm @ 6m.	pcs.	4.00					
	Wedge Anchor Bolt with Nuts and Washer, 10mmØ x 50mm x 125mm	pcs.	8.00					
	G.I. Long-Span Roofing, Corrugated, Pre-Painted, 1220mm x 0.4mm BMT	ln.m	24.00					
	J-Bolt (6mm dia.)	pcs.	48.00					
	Roof Sealant	L	3.00					
	Flashing, Pre-Painted, Ordinary, 0.915m x 2.440m x 0.4mm thk	pcs.	4.00					
	Welding Rod	kgs.	8.00					
	Fascia Board, Fiber Cement 12" x 8'	pcs.	8.00					
	Concrete Nails	kg	4.00					
	Wood Preservative, Brown	L	3.00					
	Sub-total							
9.0000	CEILING AND CARPENTRY WORKS							
	Metal Double Furring Channel (19mm x 50mm x 3m x 0.5mm thk.)	pcs.	70.00					
	Blind Rivets	pcs.	404.00					
	Finishing Screw	pcs.	223.00					
	Fiber Cement Board, 1/4" x 4' x 8' Standard Size	pcs.	15.00					
	Sub-total							
10.0000	DRY WALL PARTITION							
	Metal Stud 32mm x 102mm, 0.8mm thickness @ 3m.	pcs.	34.00					
	Fiber Cement Board, 1/4" x 4' x 8' Standard Size	pcs.	7.00					
	Blind Rivets	pcs.	202.00					
	Finishing Screw	PCS.	54.00					

	Sub-total			
10.0000	Painting Works			
	Concrete Surface,			
	Neutralizer	gal	8.00	
	Latex, Flat	gal	8.00	
	Masonry Putty	gal	8.00	
	Latex, Semi Gloss	gal	14.00	
	Roller Brush "6"	pcs.	3.00	
	Paint Brush "2"	pcs.	3.00	
	Sub-total			
11.0000	Plumbing Works			
	Concrete Counter Sink Type, with Lever Type Faucet and Complete Accessories	pcs.	1.00	
	PP-R Pipe 1/2"Ø x 4.0m	pcs.	2.00	
	PP-R Pipe 3/4"Ø x 4.0m	pcs.	1.00	
	PP-R Tee Reducer, 1" x 3/4"Ø	pcs.	1.00	
	PP-R Elbow 90° x 1/2"Ø	pcs.	2.00	
	PP-R Tee Reducer, 3/4" x 1/2"Ø	pcs.	1.00	
	PP-R Coupling, 1/2"Ø	pcs.	2.00	
	PP-R Elbow 90° x 3/4"Ø	pcs.	2.00	
	PP-R Coupling, 3/4"Ø	pcs.	2.00	
	PP-R Tee, 3/4"Ø	pcs.	1.00	
	Check Valve, Horizontal, 3/4"Ø	pcs.	1.00	
	Teflon Tape	pcs.	2.00	
	Sub-total			
12.0000	Electrical Works			
	Electrical Conduit uPVC, 32mmØ	M	80.00	
	3.5 mm² THHN Wire, Stranded	m	100.00	
	5.5 mm² THHN Wire, Stranded	m	55.00	
	3 Single Pole Wall Switches in One Switch Plate (10 AMP, 230V)	set	1.00	
	Duplex Convenience Outlet, Grounding Type, 20A, 250V	set	2.00	
	FL 2 x 40W Industrial Type	set	4.00	
	Junction Box, 4" x 4" G.I.	set	2.00	
	Circuit Breaker, 30A 2P	set	2.00	
	Circuit Breaker, 20A 2P	set	1.00	
	Electrical Tape	pc	5.00	
	Sub-total			
13.0000	FORMS AND SCAFFOLDING			
	Plywood, Marine 1/4" x 4' x 8' Standard Size	pcs.	10.00	
	2"x3"x10' Coco Lumber	pcs.	36.00	
	Sub-total			
	MATERIALS (VAT inclusive)			
	LABOR			
I.	DIRECT COST			
II.	INDIRECT COST 10% of (I)			
III.	TAX 5% of (I + II)			
IV.	TOTAL CONSTRUCTION COST (I + II + III)			565,874.28

Prepared by:

RYAN JAY L. BACON
Head, EPS

Noted by:

CESAR P. VERUNQUE
Chief, ESSD

Recommending Approval:

ARNULFO M. BALANE, CESO V
Director III

Approved by:

RAMIR B. JYTICO EdD, CESO IV
Director IV

Republic of the Philippines
Department of Education
 DEPED REGIONAL OFFICE NO. VIII

Gov't. Center, Candahug, Palo, Leyte
ISO 9001:2015 CERTIFIED

PROGRAM OF WORKS

OFFICE: DepED Regional Office No. VIII			Date:		Budget Allocation: PHP 565,874.28	
Region: VIII			Engineering and Administrative Overhead:			
Division: ADMINISTRATIVE DIVISION			Approved Budget for the Contract:		PHP 565,874.28	
Project Title: REPAIR AND REHABILITATION OF ADMINISTRATIVE DIVISION CONFERENCE ROOM			Completion Period:		30 calendar days	
			Minimum Required Manpower:			
			Project Engineer		Mason	
			Foreman		Tile Setter	
Plan: DepED Plans			Minimum Required Equipment:			
Location: DepED Regional Office No. VIII			Hand Tools		Transit Mixer	
Gov't. Center, Candahug, Palo, Leyte			Bar Cutter		Concrete Vibrator	
ITEM NO.	Item Description	Unit	Quantity	Total Cost	Remarks	
I. DIRECT COST						
1.00	GENERAL REQUIREMENTS	lot	1.00			
2.00	Demolition Work	sq.m	59.46			
3.00	Earth Works	cu.m	23.26			
4.00	Concrete Works	cu.m	9.00			
5.00	Masonry Works	sq.m	78.00			
6.00	Tile works	cu.m	38.76			
7.00	Door, windows And Glass Frame Partition	set	3.00			
8.00	Roofing Works	sq.m	22.88			
9.00	Ceiling and Carpentry	sq.m	42.84			
10.00	Dry Wall Partition	sq.m	19.38			
11.00	Painting Works	sq.m	156.00			
12.00	Plumbing Works	fix	1.00			
13.00	Electrical Works	fix	6.00			
14.00	Forms and Scaffolding	sq.m	19.38			
Sub-Total			86.58%			
II. INDIRECT COST 10% of (I)						
Overhead Expenses (0%)			0.00%			
Contingencies (0%)			0.00%			
Miscellaneous (0%)			0.00%			
Contractor's Profit (10%)			8.66%			
Sub-Total			8.66%			
III. TAX 5% of (I+II)						
Sub-Total			4.76%			
IV. TOTAL CONSTRUCTION COST (I + II + III)			100.00%			

Prepared by:

RYAN JAY L. BAGON
Head, EFS

Recommending Approval:

ARNULFO M. BALANE, CESO V
Director III

Noted by:

CESAR P. VERUNQUE
Chief, ESSD

Approved by:

RAMIR B. UYTICO EdD, CESO IV
Director IV